

Bid Item Order Quantity Report by Location - Loc. Sort w/Hours-Detail
Bid 26: Res. Sample for report

Item Code	Description	Bid Quantity	Unit	Cost Type #	Cost Type Description	Order Quantity	Unit	Approx. Unit Cost	Total Cost
# 6 CONCRETE-FOUNDATION									
3.001300	15X18 Footing	250.00	LF	Mat	Material	469.00	CY	111.10	27,775.65
				Lab	Labor	6.25	HR		
3.002500	Conc Slab 4"	1,500.00	SF	Mat	Material	19.00	CY	1.30	1,958.15
				Lab	Labor	30.00	HR		
3.003000	Fill Dirt Below Slab Sub	15.00	CF	Mat	Material	1.00	CY	15.07	226.05
				Lab	Labor	15.00	HR		
3.003500	Concrete Steps Sub-Bid	35.00	LF	Mat	Material	35.00	LF	38.70	1,354.50
				Lab	Labor	35.00	HR		
3.004800	Sand & Wire Sub-Bid	2.00	SF	Lab	Labor	2.00	HR	28.37	56.74
				Sub	Subcontract	2.00	SF		
3.030100	6X6 10/10 Wire Mesh	5.00	SF	Lab	Labor	5.00	HR	39.34	196.70
				Sub	Subcontract	1.00	RL		
3.031100	# 3 (3)Per Run-Rebar	150.00	LF	Mat	Material	26.00	PC	28.10	4,215.75
				Lab	Labor	150.00	HR		
Labor-Hours	243.25	Equip-Hours		Subcont-Hours		Other-Hours		# 6 CONCRETE-FOUNDATION =	35,783.54
# 15 PLASTERING									
9.000300	Stucco Std.Fin. 9'High	250.00	LF	Sub	Subcontract	250.00	YD	18.90	4,725.00
Labor-Hours		Equip-Hours		Subcont-Hours		Other-Hours		# 15 PLASTERING =	4,725.00
# 16 DRYWALL									
9.010700	1/2Drywall 8'H Intwall	175.00	LF	Sub	Subcontract	1,400.00	SF	4.62	808.50
Labor-Hours		Equip-Hours		Subcont-Hours		Other-Hours		# 16 DRYWALL =	808.50
# 17 WINDOWS-SLIDING DOOR									
8.001700	Door-Ext 3-0X6-8 Df 4Pan	1.00	EA	Mat	Material	1.00	EA	337.50	337.50
				Lab	Labor	2.50	HR		
Labor-Hours	2.50	Equip-Hours		Subcont-Hours		Other-Hours		# 17 WINDOWS-SLIDING DOOR =	337.50
# 31 INSULATION									
7.023400	R-19 Walls	2,500.00	SF	Sub	Subcontract	2,500.00	SF	0.36	918.75
7.023700	R-19 Ceil. Batts	1,500.00	SF	Sub	Subcontract	1,500.00	SF	0.36	551.25
Labor-Hours		Equip-Hours		Subcont-Hours		Other-Hours		# 31 INSULATION =	1,470.00
Labor-Hours	245.75	Equip-Hours		Subcont-Hours		Other-Hours		Total of Shown Bid Items *ONLY*	43,124.54

Thank You